



Fermilab Seminar 31 August 2007



Review of the Design Choices & Construction of the CMS Experiment

A. Hervé / CERN



Content



- *I will not touch on construction of sub-detectors but will concentrate on the general logistics for construction, installation and maintenance of CMS.*
- *I will just mention the coil for its implication on the choice for constructing CMS on the surface.*
- *I will not discuss the general principles of the integration project that would require a talk by itself.*
- *I will show the recent events on CMS and status of installation.*
- *I will mention, at the end, the relevance of the CMS concept and choices for new projects.*



Fermilab Seminar 31 August 2007



Part-1


Concepts behind the design of the CMS Experiment



CMS Experiment

Fermilab is a strong collaborator

CMS A Compact Solenoidal Detector for LHC



Based on Large
SC Solenoid

6 m diameter

13 m long

Strong Field 4T

10'000-ton
Instrumented
Return Yoke

Total weight : 12,500t.
Overall diameter : 15.00m
Overall length : 21.60m
Magnetic field : 4 Tesla

SUPERCONDUCTING
COIL

RETURN YOKE

CMS-PARA-001-11/07/97

JLB.PP



CMS Technical Design Principles

from experience gained on LEP detectors

- ***Sub-detectors must be maintainable, that is detector can be opened in a reasonable time to give access to every one of them, including access to the main flanges of Tracker, ECAL and HCAL.***
- ***This opening scenario must be possible without decabling or removing services of any sub-detector, to allow fast re-commissioning before closing again the detector at the end of a shut-down.***
- ***The goal is to maximize maintenance time to get all sub-detectors operating at their optimum during the whole life of the experiment, not only at the start.***




Fermilab Seminar 31 August 2007



Sectioning the experiment
and sub-detector installation
with a view to maintenance



Large elements must be able to moved Connected by large cable chains






Installation of Muon Stations/RPC package in mobile wheel1




Compatible with maintenance scenario





Installation of DT/RPC package in central wheel


Compatible with maintenance scenario





Installation of CSC/RPC package on first disk


Compatible with maintenance scenario





Installation of CSC/RPC package on first disk under nose

Compatible with maintenance scenario






Supporting the inner detectors from vactank



Inner vactank supports the 1000-tonne Hadronic Barrel and 200-ton Electromagnetic barrel on 2 rails imbedded in the shell




Penetration for current leads and pumping

There is another one for cryogenics vertical on opposite side of YB0

January 2006: End of the CMS Magnet Manufacturing



HB Insertion inside inner vacuum tank on surface




Grease pads to adjust axes

Jacks to adjust rail plane



HCAL Barrel inserted to load Vactank



Precise survey to determine **shimming and corrections to be applied for final installation underground**




Installation of EB modules inside HB

Compatible with maintenance scenario




**Use of a rotator
to feed modules
at correct
angle**





Installation of two EB modules inside HB


For testing on the surface





Installation of dummy Tracker inside HB

Compatible with maintenance scenario





Eiffel Tower to pull Tracker through EB

Compatible with maintenance scenario





Fermilab Seminar 31 Aug. 07



Construction of the the Yoke, Coil and HCAL in the Surface Hall



Construction of Surface Hall Sept. 1999 delivered mid 2000



CMS-T_Fermilab


Point 5 - SX5 gantry crane installation - September 17, 1999 - CERN ST-CE





Construction of yoke wheels started beginning of 2000 using a precise jig



Effort has been made not to align dead zones



Air pads





Construction of 600mm thick endcap disk






Construction of 600mm thick endcap disk
Generally all pieces have been carefully surveyed




CMS ENDCAP PHOTOGRAMMETRY

YE-1 Oct 2001





Also during blank assy at manufacturers..



Yoke Barrel YB0 - May 2000
Photogrametric measurement at DWE
D. Fiumbertolaude / R. Goudard




In Germany

In Japan



Each yoke element has been equipped with metallic structures to support local racks and services





In the mean time the two 500-ton HBs have been assembled directly at beam height






HB Barrels have been parked in alcoves
on the side of the building not to eat space





The Yoke has been completed in 2003 to be ready to accept the cold mass





All these activities have been carried out in the surface hall



view of SX5 after delivery in Oct. 2000

Pre-assembly of CMS in SX5 has isolated us from tricky underground Civil Engin. and schedule pressures






Why Construct CMS on the Surface ?



- *As seen at LEP, installation work takes 50% more time in a deep underground area for questions of access, limited space, superposed work areas and related safety precautions.*
- *CMS has from the start requested an assembly on the surface followed by transfer of FULLY COMMISSIONED large detector elements (up to 2000 tons) by heavy lifting means.*
- *It was also argued, and I think this has been demonstrated, that the length of the underground cavern would be insufficient to carry out such a construction work in a reasonable time.*
- *Another important argument was that all delicate or risky operations, coil test, HB insertion, EB insertion, Tracker insertion, closing of detector etc. can be carried at least once on the surface and corrections made before final operations underground.*

The coil has been assembled with vertical axis



This allows a very precise coupling

But the 220-ton coil has to be inserted inside the vacuum vessel with horizontal axis!



Coil swiveling requests large tooling




**The 220 ton
cold mass
was rotated
in 15 min**

**The coil is
maneuvered
cantilevered
from one end**



Sept. 2005: ready to insert!



CMS-T




Moving YB0 with VacTank over the Coil






Inner VacTank/Screen Insertion in Sept 2005

These operations require a free length of 30 m min.






Coil swiveling in Surface Hall August 05



*Underground
hall Detector
fully open*



Same scale!



This justifies the surface assembly



- These heavy construction activities cannot be done in a reasonable time, safely, in the underground hall.
- A much longer and wider underground hall, equipped with two 80-ton cranes, would be needed, and more time....




Fermilab Seminar 31 Aug. 07



Completing the Civil Engineering Testing of Magnet and Detectors Preparation for Transfer Underground



Construction of Main Plug on side of Shaft Apr. 04 Used as radiation protection and lifting platform






Construction of Surface Hall Extension Jul. 2004



**Removable Wall
CMS is waiting
behind..**



The plug has been tested using
a 2500 ton dead load






Survey has constantly ensured an alignment of
Elements of $\neq 1-2$ mm wrt the ideal axis






CMS Closed mid-July 2006

4T reached on 22 August 2006





A slice of all sub-detectors has been fully commissioned using cosmics






Commissioning: CMS - Cosmics Event



**CERN PRESS RELEASE
13 September 2006**


**Mammoth CMS magnet
reaches full-field at
CERN**

**Tests show CMS
detector will be ready
for data**





Elements fully commissioned ready to be lowered (for example YE+1)



Z-stops resist the 10'000-ton
attraction magnetic force

Elements are fully
cabled to local racks.
All services, gas and
water cooling pipes
are there.
Subdetectors have
been commissioned.
Once below they can
be connected to the
umbilical cables going
to the counting rooms
through the cable
chains.



Fermilab Seminar 31 August 2007




Part-2

Transfer of the CMS Experiment Underground


UX5 before receiving Elements

The cave below is used as dispatching center for cables



Design by CMS Integration group, April 2005.

Situation of cable chains before lowering Elements



Pacman

in open position


YB/YE

HF

YB/YE



How cable chains are connected to pre-cabled Elements





Installation of the 2000-ton Gantry



The gantry has been tested statically at 125% of the nominal load, that is at 2'500 tons using the plug as dead weight




350-t HF 100 m below at the bottom of the shaft



**First heavy lift with
the 350-ton Hadronic
Forward
Calorimeters Nov. 06**




500-t HB beginning the descent






500-t HB 10 hours later after a 100 m trip






Plus side stacked waiting for the central barrel



CMS-T

Opening the plug under the 2000-ton load






Lowering of the CMS detector into UXC55




Total of 15 loads from 350 to 2000 tons

**For public relations, we
used for a long time,
this view of YB0
disappearing in the
shaft....**






28 Feb. 07-YB0 at the Beginning of Descent






2000-t YB0 Crossing the Plug (2" margin)





2000-t YB0 with Coil arriving underground






1800-t Endcap Disk with Calorimetric Nose



**We had quite a good
press coverage at the
occasion of these
heavy operations!**



Coil will be Recommissioned in Spring 08



20 kA Bus Bars


6000-liter dewar

Currents Leads

Coil



HB inside Vacuum Tank






Positioning of HB and fit are perfect



**Largely due
to the test
installation
on the surface
and later
corrections**




EB module with insertion tooling






Installation of last EB module on +






Installation of EB Completed



Supports for Tracker




Today: Cabling of Tracker, HB and EB over Vacuum Tank





Today: Cabling of Tracker, HB and EB over Vacuum Tank



Tk cooling pipes

Optical fibers


LV cable trays



In parallel: Completion of Tracker in Bldg 186



**TIB + inserted into TOB +
seen from the - End
TOB - Complete**





In parallel: Completion of Tracker in Bldg 186



**TEC - Ready for insertion
into the TST**






In parallel: Completion of Tracker in Bldg 186



**- End of TST is Prepared for TEC-
TIB - has been inserted and services
dressed along TST**






In parallel: Completion of Tracker in Bldg 186



**TEC - is Installed in TST
seen from the - End**

21 March 2007






In parallel: Completion of Tracker in Bldg 186



TEC + seen from the + End

**Taking Cosmic Triggers and Preparing
the Thermal Screen to run Cold**





Tracker Completed and Commissioned



**Tracker in dry air
tent for cold running
Dew point < -14C**

**5M triggers taken at
+15, +1,-5 and -15C**





Fermilab Seminar 31 August 2007




Part-3

Operations to come & Conclusions




Tracker to be installed end October 07






Installation scenario is compatible with Tracker ultimate maintenance (removal)






Then installation of beam pipe will proceed






Expected closure of the endcaps in March and recommissioning of Magnet underground





Movement Underground on a 1.24% slope has been practiced !



Step by step system
clamping on cables




CMS will be ready to take first beam in May 08

New official LHC Schedule



VUES






If needed installation of last EE during the first Shut-down

During Shut-downs maintenance will be easy!

10 m space for access can be shared at best on each side.





Fermilab Seminar 31 Aug. 07



Conclusions



Conclusions



- **We have been able to maintain the principles adopted in 1991/1992 without any compromising.**
- **The end of CMS installation, Tracker, re-commissioning of magnet & final commissioning, is in good hand to be completed to take first beam in very good condition in May 08.**
- **The general architecture will allow an efficient maintenance as all sub-detectors can be easily accessed during a shut-down.**



Conclusions




- **The scenario of constructing on the surface followed by transfer underground looks still to us like the best solution for a detector like CMS.**
- **This option is looked at very carefully by ILC which is considering a scenario ‘à la CMS’.**



Movements of Experiment B for ILC




- 1: from surface building to main unloading zone
- 2: to garage position
- 3: beam/garage position using push-pull



One possible arrangement of an ILC experimental area for surface assembly scenario

Surface assembly hall for two experiments

2000 ton gantry





Fermilab Seminar 31 Aug. 07



Thank You!